


## May 2015 Update Pack



Dear Colleague,

Thank you for subscribing to receive updates to the Part E Robust Details Handbook.

The major focus of this update pack is the flexible cavity closer fitted in the external cavity, in line with the separating floors. Previously, this could only be omitted if the cavity was fully-filled with built-in mineral wool – but now, where the floors listed below are registered, it can also be omitted if the cavity is filled with blown mineral wool.

Also, the colour of the insulation in E-WM-28 has been changed to more accurately represent the actual material. **Please note:** if you have a newer book (purchased after February 2015), E-WM-28 may already be shown with the blue insulation, but please replace this section anyway.

### **Please update your February 2015 4th Edition Handbook as follows:**

1. Remove and replace page 7-8 in the Introduction.
2. Remove and replace all pages of E-WM-28.
3. Remove and replace just the first page of the concrete separating floors:  
E-FC-1, E-FC-3, E-FC-4 and E-FC-5.
4. Remove and replace all pages of the concrete separating floors:  
E-FC-6 and E-FC-7.
5. Remove and replace just the first page of the concrete separating floors:  
E-FC-8 and E-FC-9.
6. Remove and replace all pages of the concrete separating floor E-FC-10
7. Remove and replace just the first page of the concrete separating floors:  
E-FC-11, E-FC-12, E-FC-13, E-FC-14, E-FC-15 and E-FC-16.

*Please note that the trademark (™) has now been removed, so the new E-FC-6 is a direct replacement for the existing E-FC-6™, for example.*

Yours sincerely

A handwritten signature in black ink, appearing to read 'John Tebbit', written over a light blue horizontal line.

**John Tebbit**

Managing Director,  
Robust Details Limited





## Changes to the fourth edition following May 2015 update

---

Section Page Amendment

### Introduction

Table 4 8 Amendment to note F4 to include floating floor requirement.

### Separating Walls – Masonry

#### E-WM-28

---

All diagrams All Cavity insulation coloured blue to match actual material.

### Separating Floors – Concrete

#### E-FC-1

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-4

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-5

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-6

---

Diagram 1 2 “built in” removed from external cavity closer statement.

Diagram 2 2 “built in” removed from external cavity closer statement.

Diagram 3 3 “built in” removed from external cavity closer statement.

#### E-FC-7

---

Diagram 1 2 “built in” removed from external cavity closer statement.

Diagram 2 2 “built in” removed from external cavity closer statement.

Diagram 3 3 “built in” removed from external cavity closer statement.

#### E-FC-8

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-9

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-10

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-11

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-12

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-13

---

Diagram 1 2 “built in” removed from external cavity closer statement.

Section Page Amendment

#### E-FC-14

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-15

---

Diagram 1 2 “built in” removed from external cavity closer statement.

#### E-FC-16

---

Diagram 1 2 “built in” removed from external cavity closer statement.



# Introduction

**Table 3b – Combinations of Robust Details separating walls and floors for flats/apartments in timber frame constructions**

Separating walls	Separating floors	
	E-FT-1 E-FT-2 E-FT-3 E-FT-4 E-FT-5 E-FT-6 E-FT-7 E-FT-8	E-FC-2 E-FS-1
E-WT-1	✓	W see note 1
E-WT-2	✓	W see note 1
E-WT-3	F	W see note 1
E-WT-4	F	W see note 1

**Table 3c – Combinations of Robust Details separating walls and floors for flats/apartments in reinforced concrete and steel frame constructions**

Separating walls	Separating floors			
	E-FC-2	E-FC-10	E-FS-1	E-FS-2
E-WS-1	W see note 1	W	W see note 1	✓
E-WS-2	✓	W	W	W
E-WS-3	W	W	W	W
E-WS-4	W see note 1	W	W see note 1	✓

Key for Table 3b and Table 3c

**F** Only the separating floor requires pre-completion sound testing.

**W** Only the separating wall requires pre-completion sound testing.

**1** Lightweight steel and timber frame walls may be constructed above in-situ poured concrete floors. The lightweight walls built directly off the concrete floors may be registered as Robust Details provided:

- they meet all other requirements of the Robust Detail, including flanking constructions;
- the principles of the raft foundation junction are followed. As such, the concrete of the floor must have a mass of 365 kg/m<sup>2</sup> (min), and a floating floor treatment must be provided;

Walls constructed to the soffit of in-situ poured concrete floors cannot be registered as Robust Details and may be subject to pre-completion sound testing.

See also notes relating to [Combining loadbearing masonry and lightweight framed separating walls](#) included under Table 3a.

# Introduction

**Table 4 – Combining Robust Details separating walls with non-Robust Details separating floors in flats/apartments**

Loadbearing masonry			
E-WM-1	F1	E-WM-21	F1
E-WM-2	F1	E-WM-22	F1
E-WM-3	F1	E-WM-23	F1
E-WM-4	F1	E-WM-24	F1
E-WM-5	F1	E-WM-25	F1
E-WM-6	F1	E-WM-26	F1
E-WM-8	F1	E-WM-27	F1
E-WM-10	F1	E-WM-28	F1
E-WM-11	F1		
E-WM-12	F1		
E-WM-13	F1		
E-WM-14	F1		
E-WM-15	F1		
E-WM-16	F1		
E-WM-17	F1		
E-WM-18	F1		
E-WM-20	F1		

Timber frame		Light steel frame	
E-WT-1	F2	E-WS-1	F3
E-WT-2	F2	E-WS-2	F4
E-WT-3	F2	E-WS-3	F3
E-WT-4	F2	E-WS-4	F3

**Key**

- F1** Only the separating floor requires pre-completion testing provided the floor does not bridge the separating wall cavity. Otherwise both the wall and floor need testing.
- F2** Only the separating floor requires pre-completion testing provided the floor is timber-based and does not bridge the separating wall cavity. Otherwise both the wall and floor need testing.
- F3** Only the separating floor requires pre-completion testing provided the wall is being used in a lightweight steel frame flat/apartment and the floor does not bridge the separating wall cavity. Otherwise both the wall and floor need testing.
- F4** Only the separating floor requires pre-completion testing provided the wall is being used in a concrete frame building and the base of the wall is shielded by a floating floor treatment. Otherwise both the wall and floor need testing.

**Table 5 – Combining Robust Details separating floors with non-Robust Details separating walls in flats/apartments**

Loadbearing masonry			
E-FC-1	W1	E-FC-11	W1
E-FC-4	W2	E-FC-12	W1
E-FC-5	W2	E-FC-13	W1
E-FC-6	W1	E-FC-14	W1
E-FC-7	W1	E-FC-15	W1
E-FC-8	W2	E-FC-16	W1
E-FC-9	W2		
E-FC-10	W2		

Timber frame		RC frame	
E-FT-1	W3	E-FC-2	W4
E-FT-2	W3	E-FC-10	W4
E-FT-3	W3		
E-FT-4	W3		
E-FT-5	W3		
E-FT-6	W3		
E-FT-7	W3		
E-FT-8	W3		


		Light steel frame	
		E-FS-1	W4
		E-FS-2	W5

**Key**

- W1** Only the separating wall requires pre-completion testing provided the wall is constructed using aggregate blocks specified for the inner leaf in the floor Robust Detail. Otherwise both the floor and wall need testing.
- W2** Only the separating wall requires pre-completion testing provided the wall is constructed using blocks specified for the inner leaf in the floor Robust Detail. Otherwise both the floor and wall need testing.
- W3** Only the separating wall requires pre-completion testing if used with timber frame supporting walls and twin leaf timber frame separating walls. Otherwise both the floor and wall need testing.
- W4** Only the separating wall requires pre-completion testing provided the external wall meets the specification given in the separating floor Robust Detail. Otherwise both the floor and wall need testing.
- W5** Only the separating wall requires pre-completion testing if used with steel frame supporting walls and twin leaf steel frame separating walls. Otherwise both the floor and wall need testing.

For any construction that requires a separating element to be tested, the user should seek expert acoustic advice on the design and potential acoustic performance.

- Lightweight aggregate blocks
- Knauf Supafil Party Wall Wool
- Gypsum-based board (nominal 8 kg/m<sup>2</sup>) on dabs




<b>Block density</b>	1350 to 1600 kg/m <sup>3</sup>
<b>Wall ties</b>	Approved Document E 'Tie type A' (see Appendix A)
<b>Cavity width</b>	100mm (min)
<b>Block thickness</b>	100mm (min), each leaf
<b>Wall finish</b>	Gypsum-based board (nominal 8 kg/m <sup>2</sup> ) mounted on dabs
<b>Insulation</b>	Knauf Supafil Party Wall Wool
<b>External (flanking) wall</b>	Masonry (both leaves) with 50mm (min) cavity – clear, fully filled or partially filled with insulation


## DO

- Keep cavity and wall ties free from mortar droppings and debris
- Fully fill all blockwork joints with mortar
- Make sure there is no connection between the two leaves except for wall ties, insulation and foundation
- Ensure that only solid blocks (i.e. not hollow or cellular) are used in the construction of separating and flanking walls
- Supafil Party Wall Wool is only to be installed by contractors approved by Knauf Insulation; and must not exceed 25 kg/m<sup>3</sup> density once installed
- Ensure all injection holes are drilled through mortar joints, and made good by fully filling with mortar
- Keep any chases for services to a minimum and fill well with mortar. Stagger chases on each side of the wall to avoid them being back to back
- Refer to Appendix A

## 1. External (flanking) wall junction




- Masonry outer leaf
- External wall cavity (min 50mm)
- Close external wall cavity with a flexible cavity stop. (Optional if external wall cavity is fully filled with built in mineral wool insulation)
- Supafil Party Wall Wool
- Inner leaf where there is no separating floor e.g. for houses
  - 100mm (min) concrete block (1350 kg/m<sup>3</sup> to 1600 kg/m<sup>3</sup>) or aircrete block (450 kg/m<sup>3</sup> to 800 kg/m<sup>3</sup>)
  - internal finish – 13mm plaster or nominal 8 kg/m<sup>2</sup> gypsum-based board



- Inner leaf where there is a separating floor e.g. for flats/apartments
  - if using **robustdetails**<sup>®</sup> for floor, refer to Table 3a in introduction to select an acceptable **robustdetails**<sup>®</sup> separating floor. Then refer to separating floor Robust Detail to identify acceptable inner leaf construction
  - if using floor requiring pre-completion testing, seek specialist advice

Tooth or tie walls together


## 2. Staggered external (flanking) wall junction




- Masonry outer leaf
- External wall cavity (min 50mm)
- Inner leaf where there is no separating floor e.g. for houses
  - 100mm (min) concrete block (1350 kg/m<sup>3</sup> to 1600 kg/m<sup>3</sup>) or aircrete block (450 kg/m<sup>3</sup> to 800 kg/m<sup>3</sup>)
  - internal finish – 13mm plaster or nominal 8 kg/m<sup>2</sup> gypsum-based board
- Inner leaf where there is a separating floor e.g. for flats/apartments
  - if using **robustdetails**<sup>®</sup> for floor, refer to Table 3a in introduction to select an acceptable **robustdetails**<sup>®</sup> separating floor. Then refer to separating floor Robust Detail to identify acceptable inner leaf construction
  - if using floor requiring pre-completion testing, seek specialist advice
- Supafil Party Wall Wool
- Tooth or tie walls together
- Close external wall cavity with a flexible cavity stop. (Optional if external wall cavity is fully filled with built in mineral wool insulation)




### 3. Internal floor junction: timber floor supported on joist hangers



### 4. Internal floor junction: timber floor joists built in, beam and block or precast concrete



## 5. Separating floor junction



Supafill Party Wall Wool

Separating wall must not be continuous between storeys

5mm (min) resilient flanking strip

Concrete planks with all voids between planks and blockwork filled with mortar or flexible sealant

Separating floor must not be continuous between dwellings


Separating floor:

- if using **robust**details® for floor, refer to Table 3a in introduction and see separating floor Robust Detail for floating floor and ceiling options
- if using floor requiring pre-completion testing, seek specialist advice

Continuous horizontal ribbon of adhesive

Sketch shows E-FC-1 type separating floor, FFT1 type floating floor treatment and CT3 type ceiling

## 6. Ground floor junction: timber floor, beam and block, precast concrete plank, cast in-situ suspended concrete slab or ground bearing concrete slab



Supafill Party Wall Wool


Ground floor not continuous between dwellings

Ground floor construction:


- timber joists built in with:
  - all voids around the joists filled with mortar
  - the joint interface between the joist and the mortar sealed with flexible sealant (see Appendix A for full specification), or
- beam and block floor with all voids filled with mortar, or
- concrete planks with all voids between planks and blockwork filled with mortar or flexible sealant, or
- ground bearing slab

Cavity separating wall continuous to foundation, cavity fill may be provided below minimum clear cavity indicated. Continuous raft foundations between dwellings are not acceptable. Solid walls which support separating walls are only acceptable where each ground floor (not timber joists) is built into one side of the separating wall and breaks the vertical continuity of the wall and the minimum clear cavity indicated is maintained.

## 7. Roof junction – pitched roof without room-in-roof



## 8. Roof junction – pitched roof with room-in-roof



**CHECKLIST** (to be completed by site manager/supervisor)

Company: \_\_\_\_\_

Site: \_\_\_\_\_

Plot: \_\_\_\_\_ Site manager/supervisor: \_\_\_\_\_

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Is separating wall cavity at least 100mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Is external (flanking) wall cavity at least 50mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are separating wall blocks lightweight aggregate (1350 to 1600 kg/m <sup>3</sup> )?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Is cavity free from droppings and debris?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Are separating wall ties to Approved Document E “Tie type A” (see Appendix A)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Are cavity stops installed where specified in the Robust Detail?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are joints fully filled?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Is blue Supafil Party Wall Wool installed to a maximum density of 25 kg/m <sup>3</sup> , and was it by an approved installer?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are all injection holes drilled through the mortar joints, and made good by fully filling with mortar?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are voids around floor joists, chases, etc. fully filled/sealed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Where there is a separating floor (e.g. flats/apartments) has the resilient flanking strip been installed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Are all junctions of wall and ceiling boards sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
13.	Is separating wall satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from Knauf Insulation Ltd, manufacturer of Supafil Party Wall Wool:  
**Telephone: 01744 766 666      Fax: 01744 766 667      E-mail: [technical.uk@knaufinsulation.com](mailto:technical.uk@knaufinsulation.com)**

**Notes** (include details of any corrective action)


Site manager/supervisor signature .....

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■  
Screed ■




Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment

<b>Floating floor</b>	See section 4 for suitable floating floor treatment
<b>Screed</b>	- 40mm (min) screed directly applied to plank - cement:sand or proprietary screed nominal 80 kg/m <sup>2</sup> mass per unit area, see Appendix A
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment

### DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure floating floor treatment is suitable and install in accordance with the manufacturer's instructions
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Refer to Appendix A

## 1. External (flanking) wall junction



Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment

## 2. Separating wall junction



Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment



Performance and monitoring results of E-FC-3 have shown that, where built strictly in accordance with the published Robust Detail, the floors meet Robust Details Limited's performance criteria.

Unfortunately, the results also revealed that an unacceptably high proportion of floors deviated from the Robust Detail, which led to reduced acoustic performance to the extent that they failed under test.

**Accordingly, Robust Details Limited has determined that no new registrations for Robust Detail E-FC-3 will be accepted with effect from 1<sup>st</sup> November 2006.**

The E-FC-3 Robust Detail has therefore been removed from the Handbook.




**Dave Baker OBE**

Chief Executive, Robust Details Limited





Precast concrete plank ■  
Screed laid on Thermal Economics IsoRubber resilient layer ■




Sketch shows CT0 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	6mm IsoRubber layer with IsoEdge flanking strip
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth and supporting wall density

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **6mm IsoRubber** (resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge** flanking strip
- 3) All joints taped




- **IsoEdge** flanking strip to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

From 1 January 2009, Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 6mm IsoRubber resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 6mm IsoRubber overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)


## 1. External (flanking) wall junction



Section

Sketch shows CT0 type ceiling treatment


## 2. Separating wall junction



Section

Sketch shows CT0 type ceiling treatment

Precast concrete plank ■  
Screed laid on *Collecta*® *YELOfon*® HD10+ resilient layer system ■




Sketch shows CT0 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	<b>YELOfon</b> ® HD10+ with <b>E-strip</b> perimeter edging and <b>J-strip</b> tape for jointing
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth and block type used in supporting walls

## SYSTEM INSTALLATION:

The use of this screed resilient layer system **must** incorporate all three products:

- 1) **YELOfon**® HD10+ (resilient layer to be laid over entire floor area with min. 150mm overlaps)
- 2) **E-strip** (self adhesive perimeter edging)
- 3) **J-strip** (foamed acoustic joining tape)




- **E-strip** perimeter edging to be installed at all room perimeters. See manufacturer's guidance.
- **YELOfon**® HD10+ may also be foil faced.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from *Collecta*® on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure **YELOfon**® HD10+ resilient layer is laid over the entire floor surface and has overlapped joints of 150mm sealed with **J-strip** tape. On no account should the screed come into contact with the floor slab (See section 4 when using proprietary screeds)
- Ensure **YELOfon**® HD10+ overlaps the **E-strip** perimeter edging and joints are sealed with **J-strip** tape. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the **E-strip** perimeter edging isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)

## 1. External (flanking) wall junction




Sketch shows CT0 type ceiling treatment

## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment

- Beam and block floor with precast or in-situ edge beams
- Screed laid on Regupol E48 resilient layer system
- For use with dense aggregate block flanking walls only




<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed, nominal 80 kg/m <sup>2</sup> mass per unit area
<b>DPM</b>	0.2mm (min) waterproof membrane
<b>Resilient layer</b>	8mm Regupol E48, dimple side down, fully lapped up walls and Regupol tape for jointing
<b>Structural floor</b>	beam and block, min 100mm thick dense aggregate infill blocks, min 50mm concrete topping, min strength class C20, to floor blocks, min 300kg/m <sup>2</sup> combined mass per unit area – see section 7 for cut rows
<b>Ceiling</b>	Min 300mm from top of beam to ceiling board – see section 8

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **8mm Regupol E48** (resilient layer to be laid over entire floor area with 50mm overlaps)
- 2) All joints sealed with Regupol tape
- 3) 0.2mm (min) waterproof membrane




- **Regupol E48** must be laid dimpled side down
- **Regupol E48** must be turned up at walls and lapped under wall linings and skirtings
- Lay a 0.2mm (min) waterproof membrane over the entire floor


## DO

- Butt floor blocks tightly together
- Cover floor blocks with min 50mm concrete topping
- Ensure that concrete does not enter the cavity and bridge the two leaves of supporting wall blockwork - it is acceptable to use proprietary cavity stops to provide a shutter
- Ensure precast or in-situ edge beams are correctly installed
- Ensure in-situ concrete downstand is at least 75mm wide
- Ensure Regupol E48 is laid dimple side down, covers entire floor area and has overlapped joints sealed with Regupol tape
- Ensure Regupol E48 resilient layer isolates screed from the perimeter walls, wall linings and skirtings
- Ensure depth from top of beams to ceiling is min 300mm
- Ensure 50mm mineral fibre quilt is installed over whole ceiling board areas
- Ensure that only solid blocks (i.e. not hollow or cellular) are used in the construction of external (flanking) walls


## 1. External (flanking) wall junction – beams parallel with wall (using precast edge beams)




## 2. External (flanking) wall junction – beams parallel with wall (using in-situ concrete downstand)



### 3. External (flanking) wall junction – beams bearing on wall




### 4. Separating wall junction




Sketch shows E-WM-3 separating wall

## 5. Loadbearing internal wall – floor beams parallel to wall



## 6. Loadbearing internal wall – floor beams bearing onto wall






## 7. Floor block types

### Block types

Rebated or 'T' shape dense blocks may be used for beams of 150mm depth or greater.

Rebated or 'T' shape dense blocks may be recessed for beams of 175mm or greater.


100mm dense blocks may be used for beams of 200mm depth or greater.



### Cut rows

No more than one cut row of floor blocks may be used per room floor with minimum 25mm concrete topping.



Where a cut row junctions with perimeter walls ensure that no gap is left and that a cut block or brick slip is used to seal this junction prior to applying concrete topping.



### Wall head and floor block junctions

No gaps should remain where the last floor block junctions at the wall head.

Where the floor block does not close this gap, brick slips or cut blocks may be used.



## 8. Ceiling treatments for E-FC-6

All ceiling treatments must be installed in accordance with the manufacturer's instructions. All ceiling joints must be sealed with tape or caulked with sealant.

The minimum depth between top of beams and ceiling board **must not be less** than 300mm.

Note: the sound insulation performance of all ceiling treatments is increased if:


- resilient hangers are used
- increased thickness or density of mineral fibre quilt is used. (Do not fully fill the ceiling void with quilt.)

### Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m<sup>2</sup> of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B – Fire Safety.



### Floor depth requirements and ceiling treatments


All E-FC-6 floors must have a minimum depth of 300mm **between top of beam and ceiling board**

Only suspended metal frame ceilings systems may be used

Min 50mm mineral fibre quilt (min 10kg/m<sup>3</sup>) in the ceiling void to cover whole ceiling board area

One layer of nominal 10kg/m<sup>2</sup> gypsum-based board

## 9. Resilient layer installation



### SCREED TYPE

65mm (min) cement:sand screed or 40mm (min) proprietary screed, nominal 80 kg/m<sup>2</sup> mass per unit area


- 8mm Regupol E48 must be laid **dimpled side down**
- overlap all Regupol E48 joints (both along and across the roll) by at least 50mm and tape all joints using Regupol tape
- turn up Regupol E48 at walls to ensure screed will not touch the walls and is of sufficient length to lap under wall linings and skirtings
- lay a waterproof membrane (min 0.2mm thick) over the entire floor

## 10. Underfloor heating


Underfloor heating systems (including connectors and fixings) installed within the screed must not penetrate the resilient layer or bridge the screed to the slab.

Underfloor heating systems which have a supporting layer/board may be laid on top of the Regupol E48


Appropriate screed depth cover to the heating system must be designed for – contact underfloor heating manufacturer for guidance.



## 11. Services – service pipes through separating floor



## 12. Service - service pipes through separating floor (using precast edge beams)



blank page  
See overleaf for checklist

**CHECKLIST** (to be completed by site manager/supervisor)

Company: \_\_\_\_\_

Site: \_\_\_\_\_

Plot: \_\_\_\_\_ Site manager/supervisor: \_\_\_\_\_

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are the external wall inner leaves and separating walls of dense aggregate blockwork (min 1850-2300kg/m <sup>3</sup> )?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Are all floor blocks of dense aggregate (1850-2300kg/m <sup>3</sup> ) and tightly abutted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are min 300mm wide precast concrete edge beams, or min 75mm in-situ concrete downstands installed where the beams are parallel to the external or separating flanking walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are in-situ concrete downstand beams min 75mm wide where the beams are bearing on the external or separating flanking walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Is the concrete topping to the floor blocks at least 50mm thick?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Is the Regupol E48 dimple side down and covering the whole floor area with min 50mm overlapped joints and sealed with Regupol tape?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Is the Regupol E48 isolating the screed from the perimeter walls, wall linings and skirting?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Is the ceiling system metal frame, with min 50mm mineral fibre quilt laid over the whole ceiling and of min 300mm depth from top of beam to ceiling board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Is the ceiling board 10kg/m <sup>2</sup> and are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are service pipes wrapped in quilt and boxed with two layers of nominal 8kg/m <sup>2</sup> gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is the separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>


Contact details for technical assistance from CMS Acoustics, sole distributor of Regupol E48 resilient layer system:  
**Telephone: 01925 577711      Fax: 01925 577733      E-mail: info@cmsacoustics.co.uk**

**Notes** (include details of any corrective action)

Site manager/supervisor signature .....

©: UK registered trade mark no. 2291665  
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.  
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

- Beam and block floor with precast or in-situ edge beams
- Using floating floor treatments
- For use with dense aggregate block flanking walls only




<b>Floating floor</b>	See section 9 for suitable floating floor treatment
<b>Structural floor</b>	beam and block, min 100mm thick dense aggregate infill blocks, min 50mm concrete topping, min strength class C20, to floor blocks, min 300kg/m <sup>2</sup> combined mass per unit area – see section 7 for cut rows
<b>Ceiling</b>	Min 300mm from top of beam to ceiling board – see section 8

## DO


- Butt floor blocks tightly together
- Cover floor blocks with min 50mm concrete topping
- Ensure that concrete does not enter the cavity and bridge the two leaves of supporting wall blockwork - it is acceptable to use proprietary cavity stops to provide a shutter
- Ensure precast or in-situ edge beams are correctly installed
- Ensure in-situ concrete downstand is at least 75mm wide
- Ensure levelling screed is applied before using FFT1 or FFT3 (resilient batten) floating floor treatments (see section 9)
- Ensure quilt is inserted within FFT2 (cradle/saddle) floating floor treatment (see section 9)
- Ensure floating floor treatment is suitable and install in accordance with manufacturer's instructions
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Ensure depth from top of beams to ceiling is min 300mm
- Ensure 25mm mineral fibre quilt is installed over whole ceiling board areas
- Ensure that only solid blocks (i.e. not hollow or cellular) are used in the construction of external (flanking) walls

## 1. External (flanking) wall junction – beams parallel with wall (using precast edge beams)



- Masonry outer leaf
- External wall cavity (min 50mm)
- Inner leaf (min 100mm) dense aggregate concrete block (1850-2300kg/m<sup>3</sup>)
- 5mm (min) resilient flanking strip
- Section shows FFT3 type floating floor over 20mm (min) levelling screed (see section 9 for acceptable floating floor alternatives)
- Beam and block floor:
  - min 50mm concrete topping to all floor blocks
  - walls must not be continuous between storeys
  - floor blocks to be tightly abutted (see section 7 for floor block types)
  - precast concrete edge beam min 300mm wide must break vertical continuity of wall leaves (NB: edge beam shape may vary between manufacturers)
  - all voids between edge beam and inner leaf blockwork filled with mortar or flexible sealant
- Close cavity with a flexible cavity stop unless it is fully filled with mineral wool insulation
- Continuous horizontal ribbon of adhesive
- Nominal 8kg/m<sup>2</sup> gypsum-based board or 13mm plaster


## 2. External (flanking) wall junction – beams parallel with wall (using in-situ concrete downstand)




- Masonry outer leaf
- External wall cavity (min 50mm)
- Inner leaf (min 100mm) dense aggregate concrete block (1850-2300kg/m<sup>3</sup>)
- 5mm (min) resilient flanking strip
- Section shows FFT3 type floating floor over 20mm (min) levelling screed (see section 9 for acceptable floating floor alternatives)
- Beam and block floor:
  - min 50mm concrete topping to all floor blocks
  - walls must not be continuous between storeys
  - floor blocks to be tightly abutted (see section 7 for floor block types)
  - in-situ concrete downstand must be min 75mm wide and must break vertical continuity of wall leaves
- Close cavity with a flexible cavity stop unless it is fully filled with mineral wool insulation
- Continuous horizontal ribbon of adhesive
- Nominal 8kg/m<sup>2</sup> gypsum-based board or 13mm plaster



## 3. External (flanking) wall junction – beams bearing on wall




## 4. Separating wall junction




Sketch shows FFT3 type floating floor over 20mm (min) levelling screed and E-WM-3 separating wall

## 5. Loadbearing internal wall – floor beams parallel to wall



## 6. Loadbearing internal wall – floor beams bearing onto wall



## 7. Floor block types

### Block types

Rebated or 'T' shape dense blocks may be used for beams of 150mm depth or greater.

Rebated or 'T' shape dense blocks may be recessed for beams of 175mm or greater.


100mm dense blocks may be used for beams of 200mm depth or greater.



### Cut rows

No more than one cut row of floor blocks may be used per room floor with minimum 25mm concrete topping.



Where a cut row junctions with perimeter walls ensure that no gap is left and that a cut block or brick slip is used to seal this junction prior to applying concrete topping.



### Wall head and floor block junctions

No gaps should remain where the last floor block junctions at the wall head.

Where the floor block does not close this gap, brick slips or cut blocks may be used.



## 8. Ceiling treatments for E-FC-7

All ceiling treatments must be installed in accordance with the manufacturer's instructions. All ceiling joints must be sealed with tape or caulked with sealant.

The minimum depth between top of beams and ceiling board **must not be less** than 300mm.

Note: the sound insulation performance of all ceiling treatments is increased if:


- resilient hangers are used
- increased thickness or density of mineral fibre quilt is used. (Do not fully fill the ceiling void with quilt.)

### Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m<sup>2</sup> of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B – Fire Safety.



### Floor depth requirements and ceiling treatments

All E-FC-7 floors must have a minimum depth of 300mm **between top of beam and ceiling board**

Only suspended metal frame ceiling systems may be used

Min 25mm mineral fibre quilt (min 10kg/m<sup>3</sup>) in the ceiling void to cover whole ceiling board area

One layer of nominal 10kg/m<sup>2</sup> gypsum-based board




## 9. Floating floor treatments for E-FC-7

All floating floor treatments :

- Must achieve a minimum laboratory performance of  $rd\Delta L_w=17dB$  - see Appendix D.
- Must be installed in accordance with the manufacturer's instructions.
- Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.

d) For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.

\* Note - void dimensions indicated are when floor is loaded to 25 kg/m<sup>2</sup>.



### FFT1 – Resilient composite deep batten system with 20mm levelling screed

- 18mm (min) t&g flooring board
- resilient layer must be continuous and pre-bonded to batten
- resilient composite deep battens
- ensure any services do not bridge the resilient layer
- battens may have the resilient layer at the top or the bottom

### FFT2 – Resilient cradle and batten system with 25mm mineral fibre quilt (min 10kg/m<sup>3</sup>)

- 18mm (min) t&g flooring board
- cradle and batten
- ensure any services do not bridge the resilient layer

### FFT3 – Resilient composite standard batten system with 20mm levelling screed

- 18mm (min) t&g flooring board
- resilient layer must be continuous and pre-bonded to batten
- resilient composite standard battens
- ensure any services do not bridge the resilient layer
- battens may have the resilient layer at the top or the bottom


## 10. Underfloor heating

Underfloor heating may be used with timber floating floors FFT1, FFT2 and FFT3.


Underfloor heating must not bridge or bypass the FFT resilient layer (i.e. avoid bridging the void between the flooring board and core floor).

Rigid flooring boards must not come into direct contact with the flooring board layer.


See Appendix A for further guidance.



## 11. Services – service pipes through separating floor



## 12. Service - service pipes through separating floor (using precast edge beams)



blank page  
See overleaf for checklist

**CHECKLIST** (to be completed by site manager/supervisor)

Company: \_\_\_\_\_

Site: \_\_\_\_\_

Plot: \_\_\_\_\_ Site manager/supervisor: \_\_\_\_\_

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are the external wall inner leaves and separating walls of dense aggregate blockwork (min 1850-2300kg/m <sup>3</sup> )?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Are all floor blocks of dense aggregate (1850-2300kg/m <sup>3</sup> ) and tightly abutted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are min 300mm wide precast concrete edge beams, or min 75mm in-situ concrete downstands installed where the beams are parallel to the external or separating flanking walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are in-situ concrete downstand beams min 75mm wide where the beams are bearing on the external or separating flanking walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Is the concrete topping to the floor blocks at least 50mm thick?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has the floating floor been installed correctly where a levelling screed is required under FFT1 or 3 resilient battens or mineral wool quilt is required between the FFT2 cradles/saddles?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Has the floating floor been installed in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Have the resilient flanking strips been fitted at the floor edge perimeters?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Is the ceiling system metal frame, with min 25mm mineral fibre quilt laid over the whole ceiling and of min 300mm depth from top of beam to ceiling board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Is the ceiling board 10kg/m <sup>2</sup> and are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are service pipes wrapped in quilt and boxed with two layers of nominal 8kg/m <sup>2</sup> gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Is the separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>


**Notes** (include details of any corrective action)

Site manager/supervisor signature .....

©: UK registered trade mark no. 2291665  
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.  
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.



- Precast concrete plank
- Screed laid on resilient layers
- Bonded resilient floor cover



<b>Floor covering</b>	4.5mm (min) bonded resilient floor covering (see section 4)
<b>Screed</b>	65mm (min) sand cement screed, or 40mm proprietary screed, 80 kg/m <sup>2</sup> (min) mass per unit area
<b>Isolating layer (1)</b>	5mm foamed polyethylene layer 30-36 kg/m <sup>3</sup>
<b>Isolating layer (2)</b>	25mm mineral wool batt 140 kg/m <sup>3</sup> (min), 25mm EPS (flooring grade SD) or extruded polystyrene insulation
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth

## IMPORTANT

Bonded resilient floor coverings must be tested in accordance with Appendix G.

See section 4 for performance requirements and edge detail installation options.

Polyethylene foams may not be used for bonded resilient floor coverings.


The resilient floor covering material must be overprinted with wording prohibiting its removal.

Bonded resilient floor covering should be suitably resistant to site and removals traffic.


## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Install the 5mm and 25mm isolating layers with staggered joints
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure the isolating edge strip is 25mm mineral wool batt (min 140 kg/m<sup>3</sup>) or expanded (SD grade) or extruded polystyrene insulation board
- Ensure resilient floor cover is bonded using only suppliers' recommended adhesives, and is not readily removable


## 1. External (flanking) wall junction



Sketch shows CT0 type ceiling treatment




## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment

- 3mm Thermal Economics IsoRubber Top ■
- Precast concrete plank ■
- Screed ■




<b>Floor covering</b>	3mm Thermal Economics IsoRubber Top (bonded with IsoBond adhesive)
<b>Screed</b>	65mm (min) sand cement screed, or 40mm proprietary screed, 80 kg/m <sup>2</sup> (min) mass per unit area
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth


## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure IsoRubber Top fully covers floor area
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure IsoRubber Top is bonded to screed with IsoBond adhesive


## 1. External (flanking) wall junction



## 2. Separating wall junction



- 3mm Thermal Economics IsoRubber Top ■
- In-situ concrete slab ■
- For use in loadbearing masonry or reinforced concrete frame construction ■



Floor covering	3mm IsoRubber Top bonded to slab with IsoBond adhesive
Structural floor	175mm (min) in-situ concrete floor slab 2400 kg/m <sup>3</sup> (min) density
Ceiling	See section 4 for suitable ceiling treatment

### Reinforced concrete frame construction – alternative external (flanking) wall construction

Storey height glazing units are an acceptable alternative to the cavity walls illustrated:

- glazing units should not be continuous between storeys
- mullion or transom supports/framing should not be continuous between dwellings
- Refer to Appendix A


#### Note:

Apartments may be built with **robustdetails**<sup>®</sup> cavity masonry separating walls (refer to Table 3a of the Introduction) provided floor slab is **NOT** continuous between dwellings


### DO

- Ensure floor slab density is 2400 kg/m<sup>3</sup> (min)
- Fill all voids between walls and floor
- Ensure IsoRubber Top is fully bonded to slab with IsoBond adhesive
- Ensure IsoRubber Top fully covers floor surface
- Make sure there is a ceiling void of 150mm (min) and ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure that floor slab breaks the vertical continuity of flanking walls
- Ensure that concrete does not enter the cavity and bridge the two leaves of supporting wall blockwork – it is acceptable to use proprietary cavity stops to provide a shutter
- Refer to Appendix A


## 1. External (flanking) wall junction – loadbearing masonry construction




## 2. External (flanking) wall junction – reinforced concrete frame construction with steel or timber frame inner leaf



## 3. External (flanking) wall junction – reinforced concrete frame construction



## 4. Separating wall junction – loadbearing masonry construction



## 5. Ceiling treatment for E-FC-10

Ceiling treatment must be installed in accordance with the manufacturer's instructions.

All ceiling joints must be sealed with tape or caulked with sealant.

The maximum load on resilient bars shall not exceed that specified in the manufacturer's instructions.

Note: the sound insulation performance of ceiling treatment is increased if:


- 25mm (min) mineral wool quilt is placed in the ceiling void, and/or
- resilient hangers are used

### Downlighters and recessed lighting

Provided there is a minimum ceiling void of 150mm, downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m<sup>2</sup> of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety



### Any ceiling system – 150mm void

- any metal ceiling system providing 150mm (min) ceiling void
- one layer of nominal 10 kg/m<sup>2</sup> gypsum-based board




## 6. Underfloor heating systems within screeds

Underfloor heating systems may be installed within the screed.


Appropriate screed depth cover to the heating system must be designed for – contact underfloor heating manufacturer for guidance.

**Note:** If required it is permissible to have an insulation layer between screed and slab (as shown in Option B).


### OPTION A



### OPTION B



## 7. Services – Service pipes through separating floor



**CHECKLIST** (to be completed by site manager /supervisor)

Company: \_\_\_\_\_

Site: \_\_\_\_\_

Plot: \_\_\_\_\_ Site manager/supervisor: \_\_\_\_\_

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Is concrete slab density 2400 kg/m <sup>3</sup> (min)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Where blockwork inner leaves are adopted for the external (flanking) walls are they of the correct density?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Is concrete slab 175mm (min) thick?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Is inner leaf discontinuous between storeys?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Has ceiling system been installed in accordance with the manufacturer’s instructions (where applicable)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Is there a minimum ceiling void of 150mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are all ceiling board joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Has the IsoRubber Top been bonded to the slab with IsoBond adhesive?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Is the IsoRubber Top fully covering the floor surface?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are service pipes wrapped in quilt and boxed in with two layers of gypsum-based board, nominal 8 kg/m <sup>2</sup> each layer	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from Thermal Economics, manufacturer of IsoRubber Top:  
**Telephone: 01582 544255      Fax: 01582 429305      E-mail: [technical@thermal-economics.co.uk](mailto:technical@thermal-economics.co.uk)**


**Notes** (include details of any corrective action)

Site manager/supervisor signature .....

©: UK registered trade mark no. 2291665  
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.  
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■  
 Screed laid on Icopal-MONARFLOOR® TRANQUILT® resilient layer ■




Sketch shows CT0 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	10mm TRANQUILT®
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth and supporting wall density

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **TRANQUILT®** (resilient layer to be laid over entire floor area with integrated overlap seal)
- 2) **TRANQUILT®** to be laid with 150mm upstand at wall (to allow for isolation under wall lining and skirting after screed is poured)
- 3) **Monarfloor Acoustic Adhesive** (to affix all **TRANQUILT®** perimeter edges to slab and integrated overlap)
- 4) Butt joints which do not have integral overlap to be adhered and taped  
See section 4




## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure TRANQUILT® resilient layer is laid over entire floor surface with 150mm upstand at perimeter walls
- Ensure integrated overlap is sealed with Monarfloor Acoustic Adhesive
- Ensure all joints without integrated overlap are sealed with adhesive and taped
- Ensure correct blocks are used in construction of external (flanking) walls
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)


From 1 January 2009, Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Icopal-MONARFLOOR® on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## 1. External (flanking) wall junction




Sketch shows CT0 type ceiling treatment

## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment

Precast concrete plank ■  
 Screed laid on Thermal Economics IsoRubber Base HP3 resilient layer ■




Sketch shows CT1 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	3mm IsoRubber Base HP3 layer with IsoEdge flanking strip
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **3mm IsoRubber Base HP3** (resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge** flanking strip
- 3) All joints taped




- **IsoEdge** flanking strip to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

From 1 January 2009, Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 3mm IsoRubber Base HP3 resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 3mm IsoRubber Base HP3 overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)

## 1. External (flanking) wall junction




Sketch shows CT1 type ceiling treatment

## 2. Separating wall junction



Sketch shows CT1 type ceiling treatment

- Precast concrete plank ■
- Screed laid on InstaCoustic InstaLay 65 resilient layer ■




Sketch shows CT0 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand screed
<b>Resilient layer</b>	InstaLay 65 layer with InstaLay 65 edge strip
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **InstaLay 65** (resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **InstaLay 65** edge strip
- 3) All joints taped




- **InstaLay 65** edge strip to be installed at all room perimeters. See manufacturer's guidance.

Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from InstaCoustic on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure InstaLay 65 resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab.
- Ensure InstaLay 65 overlaps with InstaLay 65 edge strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the InstaLay 65 edge strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)

## 1. External (flanking) wall junction



Sketch shows CT0 type ceiling treatment


## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment



- Precast concrete plank ■
- Screed laid on Thermal Economics IsoRubber Code layer ■



Sketch shows CT0 type ceiling treatment


<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	6mm IsoRubber Code layer with IsoEdge 6/260 flanking strip
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment
<b>Absorbent material</b>	50mm (min) mineral wool quilt insulation 10 kg/m <sup>3</sup> (min)

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **6mm IsoRubber Code layer**  
(resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge 6/260 flanking strip**
- 3) All joints taped

### IsoEdge 6/260 flanking strip




- **IsoEdge 6/260 flanking strip** to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 6mm IsoRubber resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 6mm IsoRubber overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions

## 1. External (flanking) wall junction




Sketch shows CT0 type ceiling treatment

## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment

- Precast concrete plank
- Screed laid on Regupol Quietlay resilient layer




Sketch shows CT0 type ceiling treatment

<b>Screed</b>	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m <sup>2</sup> mass per unit area
<b>Resilient layer</b>	Regupol Quietlay
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth

## SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **Regupol Quietlay** (resilient layer to be laid over entire floor area)
- 2) **Regupol Quietlay** to be laid with min 100mm upstand at wall (to allow for isolation under wall lining and skirting after screed is poured)
- 3) All joints taped with Regupol Tape only




## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure resilient layer is laid over entire floor surface with min 100mm upstand at perimeter walls
- Ensure that 'Regupol' is printed on the resilient layer material
- Ensure all joints are taped with Regupol Tape
- Ensure correct blocks are used in construction of external (flanking) walls
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)


Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from CMS Danskin on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

## 1. External (flanking) wall junction




Sketch shows CT0 type ceiling treatment

## 2. Separating wall junction



Sketch shows CT0 type ceiling treatment

- 3mm Thermal Economics IsoRubber CC3 ■
- Precast concrete plank ■
- Screed ■




<b>Floor covering</b>	3mm Thermal Economics IsoRubber CC3 (bonded with IsoBond adhesive)
<b>Screed</b>	65mm (min) sand cement screed
<b>Structural floor</b>	Precast concrete plank of 150mm (min) thickness and 300 kg/m <sup>2</sup> (min) mass per unit area
<b>Ceiling</b>	See section 3 for suitable ceiling treatment which is dependent on floor plank depth

## DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure IsoRubber CC3 fully covers floor area
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure IsoRubber CC3 is bonded to screed with IsoBond adhesive

1. External (flanking) wall junction



2. Separating wall junction

