


April 2019 Update Pack



Dear Colleague,

Thank you for downloading the April update – you’d be a fool not to!

This update includes pre-insulated concrete panels from Nu-Span and Spantherm for use as a suspended ground floor structure. As you’ll see in the revised Table 6a, these flooring systems can be used with the vast majority of **robust**details® cavity separating walls.

A second flanking construction comes in the form of a single-leaf spandrel panel to E-WM-31, and this option can be used in place of the existing twin-leaf spandrels where required. There has also been a change to the wall tie configuration in E-WM-31.

We have also provided additional clarification on the flanking options for E-FS-3; and the wall specification used within the private stairs solution in Appendix A2.

Away from the flanking theme, “**energystore superbead**” EPS insulation is now accepted as an alternative to mineral wool for filling the cavity of E-WM-18.

Please update your January 2018, 4th Edition Handbook as follows:

1. Remove and replace **just last page 9/10** of the Introduction.
2. Remove and replace **just last page 1/2** of E-WM-18.
3. Remove and replace **all pages** of E-WM-31.
4. Remove and replace **all pages** of E-FS-3.
5. Remove and replace **page 1/2** and **page 13/14** of Appendix A2.
6. Add **page 15** to the end of Appendix A2.

Yours sincerely

John Thompson

Chief Executive,
Robust Details Limited



Changes to the fourth edition following April 2019 update

Section Page Amendment

Introduction

Table 6a 9-10 New flanking construction, Nu-Span and Spantherm ground floor planks added along with acceptable wall types.

Separating Wall – Masonry

E-WM-18

Cavity insulation 1 “energystore superbead” added as a cavity insulation option.

E-WM-31

4th bullet point 1 “SIG I-House” renamed as “RoofSpace I-House”.

Isometric 1 Wall ties increased to 3 per storey height.

Diagram 3 3 Wall tie pattern changed to 3:2:3.

Diagram 7 5 “SIG RoofSpace I-Roof” renamed as “RoofSpace I-Roof”.
Alternative single-leaf spandrel option added.

Checklist 6 Item 6 changed to 3 ties per storey height.
H+H UK added to Contacts box.

Separating Floor – Steel

E-FS-3

Diagram 1 2 Clarification on service zone option.

Checklist 6 Item 11 deleted; subsequent items renumbered.

Appendix A2

Contents 1 New flanking construction added: Nu-Span and Spantherm pre-insulated ground floor concrete slabs.

Private stairs 13 Clarification on the masonry wall construction.

Nu-Span and Spantherm 15 New flanking construction added: Nu-Span and Spantherm pre-insulated ground floor concrete slabs.

Introduction

Table 6a – Robust Detail separating walls which can be used together with the specific flanking constructions contained in Appendix A2

		BRIDGESTOP® system	Smartroof system	Wall Cap RDA2	RoofSpace I-Roof	Space4 system	Stewart Milne Sigma® Panel	NYTROOF RAPID FIT SYSTEM	Nu-Span Spantherm
Masonry walls	E-WM-1	✓		✓		✓		✓	✓
	E-WM-2	✓		✓		✓		✓	✓
	E-WM-3	✓	✓	✓	✓	✓		✓	✓
	E-WM-4	✓	✓	✓	✓	✓		✓	✓
	E-WM-5	✓	✓	✓	✓	✓		✓	✓
	E-WM-6		✓	✓	✓				✓
	E-WM-8	✓	✓	✓	✓	✓		✓	✓
	E-WM-9								
	E-WM-10		✓	✓	✓				✓
	E-WM-11	✓	✓	✓	✓	✓		✓	✓
	E-WM-12	✓	✓	✓	✓	✓		✓	✓
	E-WM-13		✓	✓	✓				✓
	E-WM-14	✓	✓	✓	✓	✓		✓	✓
	E-WM-15		✓	✓	✓				✓
	E-WM-16	✓	✓	✓	✓	✓		✓	✓
	E-WM-17	✓	✓	✓	✓	✓		✓	✓
	E-WM-18	✓		✓		✓		✓	✓
	E-WM-19	✓ see note 1				✓		✓	
	E-WM-20	✓	✓	✓	✓	✓		✓	✓
	E-WM-21	✓		✓		✓		✓	✓
	E-WM-22	✓	✓	✓	✓	✓		✓	✓
	E-WM-23	✓ see note 1	✓	✓	✓				✓
	E-WM-24	✓ see note 1	✓	✓	✓				✓
	E-WM-25			✓					✓
	E-WM-26	✓	✓	✓	✓	✓		✓	✓
	E-WM-27	✓	✓	✓	✓	✓		✓	✓
	E-WM-28	✓	✓	✓	✓	✓		✓	✓
	E-WM-29			✓					✓
	E-WM-30	✓ see note 1	✓	✓	✓				✓
	E-WM-31		✓	✓	✓				✓
	E-WM-32	✓	✓	✓	✓	✓		✓	✓

Key

1 When constructing these walls off raft foundations, the raft must have insitu concrete with 150mm minimum thickness.


See over for timber and steel frame walls

Introduction

Table 6a (continued) – Robust Detail separating walls which can be used together with the specific flanking constructions contained in Appendix A2

		Smartroof system	Kingspan TEK	Prestoplan PresPeak 60	Wall Cap RDA2	RoofSpace I-Roof	Space4 system	Stewart Milne Sigma® Panel	Lightweight external cladding systems	Nu-Span Spantherm
Timber walls	E-WT-1	✓	✓	✓	✓	✓		✓	✓	✓
	E-WT-2	✓	✓	✓	✓	✓	✓	✓	✓	✓
	E-WT-3	✓			✓	✓				✓
	E-WT-4	✓			✓	✓				✓
Steel walls	E-WS-1					✓				✓
	E-WS-2									
	E-WS-3									
	E-WS-4				✓					✓
	E-WS-5									

Dense aggregate blocks ■
Wet plaster ■



Block density	1850 to 2300 kg/m ³
Wall ties	Approved Document E “Tie type A” (see Appendix A)
Cavity width	100mm (min)
Block thickness	100mm (min), each leaf
Wall finish	13mm plaster or cement: sand render with plaster skim (min 10 kg/m ²), both sides
External (flanking) wall	Masonry (both leaves) with 50mm (min) cavity – clear, fully filled or partially filled with insulation


Separating wall cavity insulation (optional)

The cavity may be insulated with mineral wool with a maximum density of 40 kg/m³ or “**energystore superbead**” insulation.

DO

- Keep cavity and wall ties (and insulation) free from mortar droppings and debris
- Fully fill all blockwork joints with mortar
- Make sure there is no connection between the two leaves except for wall ties and foundation (and insulation)
- Ensure that only solid blocks (i.e. not hollow or cellular) are used in the construction of separating and flanking walls
- Keep any chases for services to a minimum and fill well with mortar. Stagger chases on each side of the wall to avoid them being back to back
- Select an alternative Robust Detail if flues are required in the separating wall
- Refer to Appendix A

1. External (flanking) wall junction



Masonry outer leaf

External wall cavity (min 50mm)

Close external wall cavity with a flexible cavity stop. (Optional if external wall cavity is fully filled with built in mineral wool insulation)


Inner leaf where there is no separating floor e.g. for houses

- 100mm (min) concrete block (1350 kg/m³ to 1600 kg/m³ or 1850 kg/m³ to 2300 kg/m³) or aircrete block (450 kg/m³ to 800 kg/m³)
- Internal finish - 13mm plaster or nominal 8 kg/m² gypsum-based board


Inner leaf where there is a separating floor e.g. for flats/apartments

- If using **robustdetails**[®] for floor, refer to Table 3a in introduction to select an acceptable **robustdetails**[®] separating floor. Then refer to separating floor Robust Detail to identify acceptable inner leaf construction
- If using floor requiring pre-completion testing, seek specialist advice

Tooth or tie walls together



2. Staggered external (flanking) wall junction



Masonry outer leaf

External wall cavity (min 50mm)

Inner leaf where there is no separating floor e.g. for houses

- 100mm (min) concrete block (1350 kg/m³ to 1600 kg/m³, 1850 kg/m³ to 2300 kg/m³) or aircrete block (450 kg/m³ to 800 kg/m³)
- Internal finish - 13mm plaster or nominal 8 kg/m² gypsum-based board


Inner leaf where there is a separating floor e.g. for flats/apartments

- If using **robustdetails**[®] for floor, refer to Table 3a in introduction to select an acceptable **robustdetails**[®] separating floor. Then refer to separating floor Robust Detail to identify acceptable inner leaf construction
- If using floor requiring pre-completion testing, seek specialist advice

Tooth or tie walls together

Close external wall cavity with a flexible cavity stop. (Optional if external wall cavity is fully filled with built in mineral wool insulation)

- Attached houses only ■
- H+H - Celcon Elements - thin joint ■
- Gypsum-based board (nominal 8 kg/m²) on dabs ■
- Used with 'RoofSpace I-House System' ■






Element density	575 kg/m ³
Wall ties	Wall ties must be Vista VE4, Ancon Building Products Staifix HRT4 or Clan PWT4 installed at no more than 3 ties per storey height (see section 3)
Cavity width	100mm (min)
Element thickness	100mm (min), each leaf
Wall finish	Gypsum-based board (nominal 8 kg/m ²) mounted on dabs
Insulation	100mm mineral wool maximum density 40 kg/m ³
External (flanking) wall	Celcon Elements or aircrete 450-800 kg/m ³ 50mm (min) cavity – clear, fully filled or partially filled with insulation – and masonry outer leaf

DO


- Keep cavity, insulation and wall ties free from debris
- Fully fill all joints
- Make sure there is no connection between the two leaves except for wall ties, insulation and foundation
- Ensure all insulation sections are tightly butted together and half cuts are made with a clean sharp knife and are installed in accordance with the manufacturer's instructions
- Keep any chases for services to a minimum and fill well with mortar. Stagger chases on each side of the wall to avoid them being back to back
- Refer to Appendix A

1. External (flanking) wall junction




Separating wall Elements may abutt, or be taken through to the cavity face of the inner leaf

2. Staggered external (flanking) wall junction



3. Wall tie placement




Only the following wall ties are permitted:


- Vista VE4
- Ancon Building Products Staifix HRT4
- Clan PWT4

Wall ties to be positioned following the alternating pattern shown above.


No more than 3 ties per storey-height joint




4. Internal floor junction: timber floor joists built in




5. Ground floor junction: beam and block or precast concrete plank




6. Ground floor junction: cast in-situ suspended concrete slab or ground bearing concrete slab



7. Roof junction – pitched roof without room-in-roof



Alternative detail with single spandrel panel



CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Is separating wall cavity at least 100mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Is external (flanking) wall cavity at least 50mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Is external (flanking) wall inner leaf constructed from Celcon Elements or aircrete (450 to 800 kg/m ³)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are separating wall leafs constructed from Celcon Elements or aircrete (600 to 800 kg/m ³)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Is cavity free from droppings and debris?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Are separating wall ties Vista VE4, Ancon Staifix HRT4 or Clan PWT4 installed at no more than 3 ties per storey-height joint?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are cavity stops installed where specified in the Robust Detail?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Are joints fully filled?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Is 100mm mineral wool max. 40 kg/m ³ used, with no gaps remaining?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Is spandrel wall plate fully bedded on mortar, with no air gaps?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are voids around floor joists, chases, etc. fully filled/sealed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Where the ground floor has a floating floor treatment, has the perimeter insulation been installed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
13.	Are all junctions of wall and ceiling boards sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
14.	Is separating wall satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>


Contact details for technical assistance from: H+H UK
Telephone: 01732 880580 Fax: 01732 887013 E-mail: technical@hcelcon.co.uk

Notes (include details of any corrective action)

Site manager/supervisor signature

©: UK registered trade mark no. 2291665
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

- Collecta ScreedBoard® 28 on timber sub-floor
- Use with lightweight metal frame walls only




Floating floor	Collecta ScreedBoard® 28
Floor decking	18mm thick (min) wood based board, density 600 kg/m ³ (min)
Joists	254mm (min) deep metal joists
Absorbent material	100mm (min) mineral wool quilt insulation (10-36 kg/m ³) between joists
Ceiling	See section 4 for suitable ceiling treatment


DO

- Lay quilt (min 100mm thick) between all joists, including doubled up joists, ensuring no gaps remain
- Apply Collecta SB adhesive to all ScreedBoard® 28 decking joints
- Install YELOfon® FS50 flanking angle around the perimeter of the ScreedBoard® 28 to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure ceiling treatment is fixed correctly (see section 4)
- Stagger joints in ceiling layers
- Refer to Appendix A


1. External (flanking) wall junction – masonry outer leaf



2. Separating wall junction




3. Internal wall junction



4. Ceiling treatment for E-FS-3

- The maximum load on resilient bars should not exceed that specified in the manufacturer’s instructions
- Ensure ceiling layers have staggered joints.
- Services must not puncture ceiling linings (except cables, which should be sealed around with flexible sealant)

CT1 and CT2 – Must include second ceiling



CEILING BOARD FIXINGS MUST NOT PENETRATE OR TOUCH JOISTS

16mm (min) resilient bars with CT1 and CT2

16mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) – see Appendix E

Ceiling treatment CT1

Two layers of gypsum-based board, composed of 19mm (nominal 13.5 kg/m²) fixed with 32mm screws, and 12.5mm (nominal 10 kg/m²) fixed with 42 mm screws

Ceiling treatment CT2


Two layers of gypsum-based boards composed of 15mm (nominal 12.5 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 12.5 kg/m²) fixed with 42mm screws

Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the second ceiling in accordance with the manufacturer’s instructions

Particular attention should also be paid to Building Regulations Part B - Fire Safety

CT3 – Optional second ceiling



Collecta® HP30 30mm deep metal resilient bar fixed perpendicular to floor joists at 600mm (max) centres

Ceiling treatment CT3

Two layers of gypsum-based boards composed of 15mm (nominal 12.5 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 12.5 kg/m²) fixed with 42mm screws

Downlighters and recessed lighting


Downlighters or recessed lighting may be installed in the primary ceiling:

- in accordance with the manufacturer’s instructions
- at no more than one light per 2m² of ceiling area in each room unless the use of a greater density of light fittings is supported by testing undertaken in accordance with Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm


Particular attention should also be paid to Building Regulations Part B - Fire Safety

Note: Only downlighters which have been satisfactorily assessed in accordance with the procedure described in Appendix F “Determination of the acoustic performance of downlighters and recessed lighting in lightweight separating floors” are acceptable.

5. Underfloor heating systems below ScreedBoard®



6. Services – pipes through separating floor



CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are metal joists minimum 254mm deep?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Is sub-deck minimum 18mm, 600 kg/m ³ ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are YELOfon® FS50 flanking angles installed correctly?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has the ScreedBoard® 28 floating floor treatment been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Where underfloor heating is used, is FIBREfon® 8 installed in addition to the ScreedBoard® 20?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Are the correct type of resilient ceiling bars used and fitted, in accordance with the manufacturer’s instructions, at right angles to the joists (Cellecta® HP30 bars must be used if second ceiling is not included)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Has quilt (min 100mm thick) been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Has ceiling system been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are the ceiling treatments fixed to the resilient bars with correct screws, such that the screws do not touch or penetrate the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	For CT1 or CT2 is secondary ceiling void minimum 150mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 16 kg/m ² ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
13.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from Cellecta, manufacturer of ScreedBoard® 28 system:
Telephone: 01634 296677 Fax: 01634 226630 E-mail: technical@cellecta.co.uk

Notes (include details of any corrective action)

Site manager/supervisor signature

© UK registered trade mark no. 2291665
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Appendix A2 – Specific Flanking Conditions


Contents

Section	Page
Icopal-MONARFLOOR® BRIDGESTOP® System for robustdetails ® masonry cavity walls	2
Smartroof complete Interlocking “room-in-roof” panel system using robustdetails ® timber or masonry cavity walls	3
Kingspan TEK inner leaf flanking condition for robustdetails ® timber separating walls	4
Prestoplan PresPeak 60 interlocking single spandrel panel system for robustdetails ® timber separating walls	5
Icopal-MONARFLOOR® Wall Cap RDA2 System for robustdetails ® separating floors with cavity flanking walls	6
RoofSpace I-Roof™ “room-in-roof” panel system using robustdetails ® timber or masonry cavity walls	7
Space4 “room-in-roof” panel system using robustdetails ® timber or masonry cavity walls	8
Stewart Milne Timber Systems Sigma® Roof Spandrel Panel System for robustdetails ® timber separating walls	9
NYTROOF RAPID FIT SYSTEM for robustdetails ® masonry cavity walls	10
Lightweight external cladding for robustdetails ® timber separating walls	11
Flanking construction to robustdetails ® precast concrete separating floors around private stairs	12
Nu-Span and Spantherm pre-insulated ground floor concrete slabs for use on robustdetails ® cavity separating walls	15


Appendix A2 – Specific Flanking Conditions

Icopal-MONARFLOOR® BRIDGESTOP® System for robustdetails® cavity masonry walls.
Refer to Table 6 in Introduction.


1. Separating wall – direct support on raft




2. Separating wall – suspended floor with gas membrane



3. Insulated raft foundation



4. Stepped foundation



Key

- 1 500mm wide (or 250mm where shown) MONARFLOOR® BRIDGESTOP® 3mm HP Acoustic Membrane laid under the party wall over the dpm. This is an integral part of the system.
- 2 MONARFLOOR® BRIDGESTOP® Quilt in two lifts to prevent mortar droppings touching both masonry leaves.
- 3 MONARFLOOR® BRIDGESTOP® Tie to penetrate at max 450mm centres. Ties are reversible. May also be used as render depth marker.
- 4 MONARFLOOR® 6mm Flanking Band forming a 90° angle to isolate floating floor treatment from separating wall blocks, lining and skirting board.
- 5 Continuous dpm over the raft where ground gasses are an issue. Contact Icopal for specification.

- a Min 100mm block (with appropriate Type A wall ties) dependent on Robust Detail being used. Refer to Table 6a in the Introduction.
- b Min 75mm or 100mm cavity width dependent on Robust Detail being used.
- c Wall finish dependent on Robust Detail used.
- d Floating screed on insulation; or timber floating floor types FFT2 resilient cradle and batten, FFT3 resilient batten, or FFT4 deep platform system.
- e 150mm (min) thick insitu concrete 365kg/m² (min) mass per unit area or Insulslab SFRC.

Contact details for Icopal-MONARFLOOR®:

Telephone: 0161 866 6540

Fax: 0161 865 8433


E-mail: acoustics.uk@icopal.com

BRIDGESTOP® is the subject of Patent Application ref GB2429719


The trade marks MONARFLOOR and BRIDGESTOP are the subject of UK trade mark registrations owned by Icopal Limited

Appendix A2 – Specific Flanking Conditions

Section A - cavity walls




Section A - solid walls




Appendix A2 – Specific Flanking Conditions

Section B - common junctions at stair landing
Timber stairs




Joint filled and sealed with
grout or mortar





Section B - common junctions at stair landing
Concrete stairs

Joint filled and sealed with
grout or mortar



Joint filled and sealed with
grout or mortar





Alternative Detail at Floor/Stair Junction
(can be used with any of the
four configurations shown above)


Appendix A2 – Specific Flanking Conditions

Nu-Span and Spantherm pre-insulated ground floor concrete slabs for **robust**details® cavity separating walls. Refer to Table 6 in Introduction.

1. Slab installation - ground floor only



2. Slab components



Key

- 1 Nu-Span or Spantherm pre-insulated slab, 300mm or 375mm deep. Slabs can be end-bearing or side-bearing.
- 2 Nominal 10mm self-levelling compound. Thicker screed layers are also acceptable.
- a **robust**details® separating wall. Refer to Table 6a in the Introduction and relevant Robust Detail in the Handbook
- b Maintain minimum cavity width specified for chosen **robust**details® separating wall. This can be insulated in accordance with the specification for the chosen wall type.

Contact details for Nu-Span:

Telephone: 01842 810445
E-mail: info@nu-span.com
Web: www.nu-span.com

Contact details for Spantherm:

Telephone: 01636 831043
E-mail: spantherm@creaghconcrete.com
Web: www.creaghconcrete.com